CAPSULE SUMMARY SHEET

Survey No.: CH-62 (PACS C115) Construction Date: circa 1830, 1906

Name: Christ Episcopal Church

Location: 100 Block of Charles Street, La Plata, Charles County

Private/Religious/Occupied/Excellent/Restricted

Description:

Christ Episcopal Church was previously inventoried by the Maryland Historical Trust in the 1970s; however, an extensive survey form was not completed. Christ Episcopal Church is a 1½-story Victorian Gothic Revival Church on the north side of Charles Street in downtown La Plata, Charles County. The church was originally constructed circa 1830 next to the courthouse in the town of Port Tobacco, replacing an earlier church destroyed in a storm. In 1906, after the Charles County seat had been moved from Port Tobacco to La Plata, the church was dismantled, moved to La Plata, and rebuilt in the Victorian Gothic Revival style. The church has a nave and side aisles, a centered arched entry, and an off-center 4-story bell tower at the southwest corner. In 1938, a parish hall was constructed and connected to the church by a hyphen. The structure has an asphalt shingle, dual-pitch front-gable roof with five dormers on both roof planes. The church is of stone construction. All windows, including the dormer windows, are gothic-arch windows with stained glass, and there is a large gothic-arch windows on the first three stories and gothic-arch louvers on the top level. The west and east elevations have four gothic-arch windows. and a projecting bay at the rear of the church. The bay on the west elevation has a wood door and steps to grade. The parish hall, which is oriented perpendicular to the church, has an asphalt shingle, front-gable roof, an arched entry, and buttresses on the south and north elevations. The parish hall is of stuccoed concrete block construction, and it is connected to the church at the southwest corner. The windows are 8-light casements, and there are two exit doors at the rear.

Significance:

Christ Episcopal Church was erected in downtown La Plata in 1906, using building materials from the previous Christ Episcopal Church, located in Port Tobacco. The congregation is one of the oldest in the area, originally established by act of the provincial assembly in 1692. Although the building has undergone some alterations, it is a good examples of a late Victorian Gothic church.

Survey No.: CH-62 (PACS C115)

Maryland Historical Trust Maryland Inventory of Historic Properties Form U.S. 301 South Corridor Transportation Study

DOE	ves	no

1. Name: (inc	dicate preferred name)		
	Episcopal Church		
and/or common			
2. Location:			
street & number	er 100 Block of Charles !	Street not for p	ublication
city, town La F	Plata vicinity of	congressional distri	ct
state Maryland		county Charles	
3. Classificati	ion:		
Category	Ownership	Status	Present Use
_district	_public	<u>x</u> occupied	_agriculture _museum
\underline{x} building(s)	<u>x</u> private	_unoccupied	_commercial _park
	_both	_work in progresse	ducationprivate
	Public Acquisition		_entertainment residence
_object	_in process	<u>x</u> yes: restricted governme	
		eredyes: unrestricted	_industrial _scientific
	<u>x</u> not applicab	oleno	_military _other:
			_transportation
4. Owner of I	Property: (give names a	nd mailing addresses of all ow	vners)
	f Port Tobacco Parish		
street & number	er P.O. Box 760		telephone no.
city, town La F	Plata		state and zip code MD 20640
5. Location of	f Legal Description		
Land Records	Office of Charles County	1	liber 1:
	er 101 Catalpa Drive		folio 129
city, town La F	Plata		state MI
	ition in Existing Histori		
title Inventory	of Historic Sites in Calve	ert, Charles, and St. Mary's Co	ounties
date 1980			federal <u>x</u> statecountyloca
	vey records Maryland His	storical Trust	
city, town Crov	wnsville		state Maryland

7. Description Survey No.: CH-62 (PACS C115) Condition Check one Check one x excellent deteriorated unaltered _original site _good ruins x altered x_moved date of move 1906 fair unexposed

Resource Count: 1

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Christ Episcopal Church was previously inventoried by the Maryland Historical Trust in the 1970s; however, an extensive survey form was not completed. Christ Episcopal Church is a 1½-story Victorian Gothic Revival Church on the north side of Charles Street in downtown La Plata, Charles County. The church was originally constructed circa 1830 next to the courthouse in the town of Port Tobacco, replacing an earlier church destroyed in a storm. In 1906, after the Charles County seat had been moved from Port Tobacco to La Plata, the church was dismantled, moved to La Plata, and rebuilt in the Victorian Gothic Revival style. The church has a nave and side aisles, a centered arched entry, and an off-center 4-story bell tower at the southwest corner. In 1938, a parish hall was constructed and connected to the church by a hyphen.

The structure has an asphalt shingle, dual-pitch front-gable roof with five dormers on both roof planes. The church is of stone construction. All windows, including the dormer windows, are gothic-arch windows with stained glass, and there is a large gothic-arch window with a centered rose window on the south, or front elevation. The exposed elevations of the bell tower have gothic-arch windows on the first three stories and gothic-arch louvers on the top level. The west and east elevations have four gothic-arch windows, and a projecting bay at the rear of the church. The bay on the west elevation has a wood door and steps to grade.

The parish hall, which is oriented perpendicular to the church, has an asphalt shingle, front-gable roof, an arched entry, and buttresses on the south and north elevations. The parish hall is of stuccoed concrete block construction, and it is connected to the church at the southwest corner. The windows are 8-light casements, and there are two exit doors at the rear.

There are no outbuildings associated with this property.

The property is located at the corner of Charles Street and Church Street in downtown La Plata. There is a residence now used as an office to the west, and parking lots for county buildings to the north. There are some mature trees located in front of the church along Charles Street. The property's setting is downtown La Plata, along the heavily traveled main street.

8. Significance			Survey No.: CH-62	(PACS C115)
Period Areas of Signific	cance—Check and j	ustify below		
_prehistoric _archaeology-prehiste	oric_Community plan	ning _landscape ar	chitecture_religion	
_1400-1499 _archeology-historic	_conservation	_law	_science	
	_economics	_literature	_sculpture	
_1600-1699 _architecture	_education	_military	_social/	
_1700-1799	_engineering	g _music	humanitarian	
_1800-1899 _commerce	_exploration/settleme	ent _philosophy	_theater	
x 1900- communication	_industry	_politics/government	_transportation	
	_invention		_other:	
Specific dates circa 1830, 1906		Builder/Arch	itect	
check: Applicable Criteria: _ and/or	_A _B _C	_D	-	
Applicable Excep	ptions: _A _B	_C _D _E	_F _G	
Level of Significa	ance:national	_state _local		

Prepare both a summary paragraph of significance and a general statement of history and support.

Christ Episcopal Church was erected in downtown La Plata in 1906, using building materials from the previous Christ Episcopal Church, located in Port Tobacco. The congregation is one of the oldest in the area, originally established by act of the provincial assembly in 1692.

Religious architecture in the project area frequently melded vernacular residential building types with religious architectural elements such as bell towers and front-gable orientation. The degree of architectural pretension exhibited by the churches of the area depended upon congregation size, wealth, and denomination. The design of churches reflected both functional and symbolic concerns. Churches (as opposed to meeting houses) in the area, as well as the nation, almost invariably featured front-gables. The front-gable orientation was the logical exterior architectural accommodation of the lengthened nave so frequently utilized by denominations tracing their lineage ultimately to the Roman Catholic Church, rather than Eastern Orthodox Church. A bell tower not only called parishioners to worship, but also provided a visual symbol of the building's spiritual, rather than secular, function. Fenestration also frequently symbolized the building's function; rounded, Gothic arch, and pointed shapes helped distinguish the church from its secular neighbors.

Christ Episcopal Church was rebuilt in a Victorian Gothic Revival style. Most Catholic and Episcopalian churches built from 1845 to 1900 were built in the Gothic Revival style. The emergence of this style reflected the renewed religious intensity in the second quarter of the nineteenth century which is commonly referred to as the "Second Great Awakening". Religious leaders increasingly came to believe that the prevailing Greek Revival style was too pagan and that a more appropriate design would be one that harkened back to the religious spirit of the Middle Ages. Gothic Revival was also known as a picturesque style in that it rejected classical qualities and appealed to those which excited the Romantic mind. Vernacular Gothic Revival churches frequently featured pointed arches and a steeple but few of the embellishments found in urban examples. There was also an emphasis on verticality, which was achieved by steeply pitched roofs. The major variations involved the location of the steeple which, in turn, influenced the fenestration. Churches with the steeple located at the center of the facade have symmetrical fenestration with a three bay organization. They sometimes have an exposed gable in which the steeple is set behind the gable which is then frequently ornamented with stickwork.

MARYLAND HISTORICAL TRUST STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Christ Episcopal Church

SURVEY NO.: CH-62 (PACS C115)

ADDRESS: 100 Block of Charles Street, La Plata, Charles County

8. Significance (Continued)

shingling, or a round window. Placing the steeple away from the center of the facade resulted in asymmetrical fenestration and allowed room for paired windows or a triple window. The most elaborate variation featured a pair of steeples one located on each side of the church (Gottfried 1988: 250-254).

Christ Episcopal Church is located in Charles County in southern Maryland. The Native American inhabitants of southern Maryland from the Piscataway and Potobac nations were joined by European settlers beginning in 1634 with the establishment of St. Mary's City by Leonard Calvert. Successive waves of colonists took up tracts of land further inland from the Chesapeake Bay along the Patuxent and Potomac rivers and their tributaries. Charles County was formed in 1658 and Prince George's County was established in 1696. Settlement was confined to inland areas until road clearing began in the mid-eighteenth century as a result of the establishment of port towns and Maryland's rising population. Tobacco cultivation dominated the economic and social life of both Charles and Prince George's counties until the mid-nineteenth century when soil exhaustion necessitated agricultural diversification. The introduction of rail lines in 1873 linked Prince George's and Charles counties with the surrounding area, encouraging trade and settlement. While the suburbanization of Prince George's and Charles counties was ensured by the widespread availability of the automobile in the mid-twentieth century, these southern Maryland counties have also retained their rural and agricultural character.

Page 8.1 P.A.C. Spero & Company and EHT Traceries, Inc. September 1996/revised November 1998/February 2000

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM
RESOURCE NAME: Christ Episcopal Church

SURVEY NO.: CH-62 (PACS C115)

ADDRESS: 100 Block of Charles Street, La Plata, Charles County

8. Significance (Continued)

NATIONAL REGISTER EVALUATION

Christ Episcopal Church is a contributing resource within the La Plata Historic District (CH-326). Christ Episcopal Church is eligible under Criterion A, as being both a significant landmark in La Plata and the home church to one of the oldest congregations in the area. The ca. 1830 church had been relocated to La Plata from Port Tobacco in 1906 and has remained an important landmark within La Plata since the beginning of the 20th century. In addition, the Christ Episcopal Church is eligible under Criterion C, as a good example of the Victorian Gothic Revival in Southern Maryland. The church was constructed using building materials from the previous Christ Episcopal Church located in Port Tobacco and the building's design was a reflection of the functional and symbolic concerns of that time. Historic research indicates that the property has no association with persons who have made specific contributions to history, and therefore, it does not meet Criterion B. Criterion D was not assessed during this study.

Eligibility Recommended	MARYLAND HISTORICAL TRUSTEligibility Not Recommended	
Reviewer, OPS:Reviewer, NR Program:	Date: Date:	

Page 8.2 P.A.C. Spero & Company and EHT Traceries, Inc. September 1996/revised November 1998/February 2000

9. Major Bibliographical References

See Continuation Sheet

10. Geographical Data

Acreage of nominated property _ Quadrangle name <u>La Plata, MD</u>

Quadrangle scale 1:24,000

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries						
state	code	county	code			
state	code	county	code			

11. Form Prepared By

name/title Caroline Hall/Ryan McKay/Simone M. Moffett

organization P.A.C. Spero & Company/EHT Traceries, Inc. date September 1996/revised November 1998/February 2000 street & number 40 W. Chesapeake Avenue, Suite 412/5420 Western Avenue telephone (410) 296-1635/(301)656-5283

city or town Baltimore/Chevy Chase

state Maryland

Survey No.: CH-62 (PACS C115)

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposed only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

DHCP/DHCD 100 Community Place

Crownsville, MD 21032-2023 (410) 514-7600

MARYLAND HISTORICAL TRUST STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Christ Episcopal Church

SURVEY NO.: CH-62 (PACS C115)

ADDRESS: 100 Block of Charles Street, La Plata, Charles County

9. Major Bibliographical References (Continued)

Brown, Jack D., et al. Charles County, Maryland, A History. Charles County Bicentennial Committee, 1976.

Charles County Retired Teachers Association. <u>A Legacy: One- and Two-Room Schools in Charles</u> <u>County</u>. La Plata: Dick Wildes Publishing Company, 1984.

Gottfried, Herbert and Jennings, Jan. <u>American Vernacular Design, 1870-1940</u>. Ames, Iowa: Iowa State University Press. 1988.

Klapthor, Margaret Brown, and Paul Dennis Brown. <u>The History of Charles County, Maryland</u>. La Plata: Charles County Tercentenary, Inc., 1958.

Martenet, Simon J. Martenet's Map of Maryland, Atlas Edition. Baltimore, 1866.

Maryland Geological Survey. [1840] Map of Eastern Maryland with 1860 Additions. Copy on file Trust, Crownsville, MD.

at Maryland Historical

Rivoire, J. Richard. <u>Homeplaces, Traditional Domestic Architecture of Charles County, Maryland</u>. Maryland Studies Center, 1990.

La Plata: Southern

Wearmouth, John M. <u>Charles County Railroad</u>. An unpublished paper on deposit at the Prince George's County Historical Society. August 1984.

1bid. La Plata, Maryland, 1888-1988, 100 Years, The Heart of Charles County. La Plata: Town of La Plata, 1988.

Page 9.1 P.A.C. Spero & Company and EHT Traceries, Inc. September 1996/revised November 1998/February 2000

CAPSULE SUMMARY SHEET

Survey No.	: <u>CH-62 (PACS</u>	S C115)	Cons	truction Date:	circa 1830,	1906
Name: Chr	ist Episcopal	Church				
Location:	100 Block of	Charles Stree	et, La Pla <u>ta,</u>	Charles County	/	

Private/Religious/Occupied/Excellent/Restricted

Description:

Christ Episcopal Church was previously inventoried by the Maryland Historical Trust in the 1970s; however, an extensive survey form was not completed. Christ Episcopal Church is a 1½-story Victorian Gothic Revival Church on the north side of Charles Street in downtown La Plata, Charles County. The church was originally constructed circa 1830 next to the courthouse in the town of Port Tobacco, replacing an earlier church destroyed in a storm. In 1906, after the Charles County seat had been moved from Port Tobacco to La Plata, the church was dismantled, moved to La Plata, and rebuilt in the Victorian Gothic Revival style. The church has a nave and side aisles, a centered arched entry, and an off-center 4-story bell tower at the southwest corner. In 1938, a parish hall was constructed and connected to the church by a hyphen. The structure has an asphalt shingle, dual-pitch front-gable roof with five dormers on both roof planes. The church is of stone construction. All windows, including the dormer windows, are gothic-arch windows with stained glass, and there is a large gothic-arch window with a centered rose window on the south, or front elevation. The exposed elevations of the bell tower have gothicarch windows on the first three stories and gothic-arch louvers on the top level. The west and east elevations have four gothic-arch windows, and a projecting bay at the rear of the church. The bay on the west elevation has a wood door and steps to The parish hall, which is oriented perpendicular to the church, has an asphalt shingle, front-gable roof, an arched entry, and buttresses on the south and north elevations. The parish hall is of stuccoed concrete block construction, and it is connected to the church at the southwest corner. The windows are 8-light casements, and there are two exit doors at the rear.

Significance:

Christ Episcopal Church was erected in downtown La Plata in 1906, using building materials from the previous Christ Episcopal Church, located in Port Tobacco. The congregation is one of the oldest in the area, originally established by act of the provincial assembly in 1692. The structures are undistinctive examples of a common architectural style which have been altered by additions. The rebuilt Christ Episcopal Church does not represent a distinctive example of a late Victorian Gothic church.

Survey No.: CH-62 (PACS C115)

DOE ___yes ___no

	Historical Trust
Marvland	Inventory of Historic Properties Form South Corridor Transportation Study
.S. 301	South Corridor Transportation Study

- Nome i				
1. Name:	(indicate preferred	name)		
historic Christ	Episcopal Church			
and/or common				
2. Locat	ion:		-	
street & number	100 Block of Charles St	not fo	r publication	
			•	
city, town La Pl	.ata vicinity o	of congressio	nal district	
state Maryland		county Charles		
3. Class	sification:			
		Status _x_occupiedunoccupiedwork in progress Accessible _x_yes: restrictedyes: unrestrictedno (give names and maili	tele	ephone no.:
		Doconintion	state and zip cod	MD 20646
5. Locat	ion of Legal	Desci Thriaii		
Land Records Off	ice of Charles County			liber 15
street & number	101 Catalpa Drive			folio 129
city,town La Pla	ta			state MD
6. Repre	sentation in	Existing Hist	orical Surv	eys
title Inventory	of Historic Sites in Cal	Lvert, Charles, and St. M	ary's Counties	
date 1980		federal	x_statecounty	local
- ∍pository/surve	y records Maryland Histo	orical Trust		
city,town Crowns	ville		sta	ite Maryland

7. Description

 Condition
 Check one
 Check one

 __excellent
 __deteriorated
 __unaltered
 __original site

 __good
 __ruins
 _xaltered
 _xmoved
 date of move _1906

 __fair
 __unexposed

Survey No.: CH-62 (PACS C115)

Resource Count: 1

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Christ Episcopal Church was previously inventoried by the Maryland Historical Trust in the 1970s; however, an extensive survey form was not completed. Christ Episcopal Church is a $1\frac{1}{2}$ -story Victorian Gothic Revival Church on the north side of Charles Street in downtown La Plata, Charles County. The church was originally constructed circa 1830 next to the courthouse in the town of Port Tobacco, replacing an earlier church destroyed in a storm. In 1906, after the Charles County seat had been moved from Port Tobacco to La Plata, the church was dismantled, moved to La Plata, and rebuilt in the Victorian Gothic Revival style. The church has a nave and side aisles, a centered arched entry, and an off-center 4-story bell tower at the southwest corner. In 1938, a parish hall was constructed and connected to the church by a hyphen.

The structure has an asphalt shingle, dual-pitch front-gable roof with five dormers on both roof planes. The church is of stone construction. All windows, including the dormer windows, are gothic-arch windows with stained glass, and there is a large gothic-arch window with a centered rose window on the south, or front elevation. The exposed elevations of the bell tower have othic-arch windows on the first three stories and gothic-arch louvers on the top level. The lest and east elevations have four gothic-arch windows, and a projecting bay at the rear of the church. The bay on the west elevation has a wood door and steps to grade.

The parish hall, which is oriented perpendicular to the church, has an asphalt shingle, front-gable roof, an arched entry, and buttresses on the south and north elevations. The parish hall is of stuccoed concrete block construction, and it is connected to the church at the southwest corner. The windows are 8-light casements, and there are two exit doors at the rear.

There are no outbuildings associated with this property.

The property is located at the corner of Charles Street and Church Street in downtown La Plata. There is a residence now used as an office to the west, and parking lots for county buildings to the north. There are some mature trees located in front of the church along Charles Street. The property's setting is downtown La Plata, along the heavily travelled main street.

8. Significance

Period	Annan of Cian	ificence Check and ive	tifu balaw	
_prehistor: 1400-149 1500-159 1600-169 1700-179 1800-189	icarchaeology-prehistor: 99archeology-historic 99agriculture 99architecture		landscape architecturlawliteraturemilitarymusic	rereligionsciencesculpturesocial/ humanitariantheatertransportationother:
Specific o	dates circa 1830, 1906	*1 *	Builder/Architect	
check:	and/or	:ABC ns:ABC	DEFG	

Survey No.: CH-62 (PACS C115)

local

state

Prepare both a summary paragraph of significance and a general statement of history and support.

Level of Significance: ___national

Christ Episcopal Church was erected in downtown La Plata in 1906, using building materials from the previous Christ Episcopal Church, located in Port Tobacco. The congregation is one of the oldest in the area, originally established by act of the provincial assembly in 1692.

eligious architecture in the project area frequently melded vernacular residential building types with religious architectural elements such as bell towers and front-gable orientation. The degree of architectural pretention exhibited by the churches of the area depended upon congregation size, wealth, and denomination. The design of churches reflected both functional and symbolic concerns. Churches (as opposed to meeting houses) in the area, as well as the nation, almost invariably featured front-gables. The front-gable orientation was the logical exterior architectural accommodation of the lengthened nave so frequently utilized by denominations tracing their lineage ultimately to the Roman Catholic Church, rather than Eastern Orthodox Church. A bell tower not only called parishioners to worship, but also provided a visual symbol of the building's spiritual, rather than secular, function. Fenestration also frequently symbolized the building's function; rounded, Gothic arch, and pointed shapes helped distinguish the church from its secular neighbors.

Christ Episcopal Church was rebuilt in a Victorian Gothic Revival style. Most Catholic and Episcopalian churches built from 1845 to 1900 were built in the Gothic Revival style. The emergence of this style reflected the renewed religious intensity in the second quarter of the nineteenth century which is commonly referred to as the "Second Great Awakening". Religious leaders increasingly came to believe that the prevailing Greek Revival style was too pagan and that a more appropriate design would be one that harkened back to the religious spirit of the Middle Ages. Gothic Revival was also known as a picturesque style in that it rejected classical qualities and appealed to those which excited the Romantic mind. Vernacular Gothic Revival churches frequently featured pointed arches and a steeple but few of the embellishments found in urban examples. There was also an emphasis on verticality, which was achieved by steeply pitched roofs. The major variations involved the location of the steeple which, in turn, influenced the fenestration. Churches with the steeple located at the center of the facade have /mmetrical fenestration with a three bay organization. They sometimes have an exposed gable in which the steeple is set behind the gable which is then frequently ornamented with stickwork,

MARYLAND HISTORICAL TRUST STATE HISTORIC SITES INVENTORY FORM RESOURCE NAME: Christ Episcopal Church

SURVEY NO.: CH-62 (PACS C115)

ADDRESS: 100 Block of Charles Street, La Plata, Charles County

8. Significance (Continued)

shingling, or a round window. Placing the steeple away from the center of the facade resulted in asymmetrical fenestration and allowed room for paired windows or a triple window. The most elaborate variation featured a pair of steeples one located on each side of the church (Gottfried 1988: 250-254).

Christ Episcopal Church is located in Charles County in southern Maryland. The Native American inhabitants of southern Maryland from the Piscataway and Potobac nations were joined by European settlers beginning in 1634 with the establishment of St. Mary's City by Leonard Calvert. Successive waves of colonists took up tracts of land further inland from the Chesapeake Bay along the Patuxent and Potomac rivers and their tributaries. Charles County was formed in 1658 and Prince George's County was established in 1696. Settlement was confined to inland areas until road clearing began in the mid-eighteenth century as a result of the establishment of port towns and Maryland's rising population. Tobacco cultivation dominated the economic and social life of both Charles and Prince George's counties until the mid-nineteenth century when soil exhaustion necessitated agricultural diversification. The introduction of rail lines in 1873 linked Prince George's and Charles counties with the surrounding area, encouraging trade and settlement. While the suburbanization of Prince George's and Charles counties was ensured by he widespread availability of the automobile in the mid-twentieth century, these southern waryland counties have also retained their rural and agricultural character.

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM RESOURCE NAME: Christ Episcopal Church

SURVEY NO.: CH-62 (PACS C115)

ADDRESS: 100 Block of Charles Street, La Plata, Charles County

8. Significance (Continued)

NATIONAL REGISTER EVALUATION

Christ Episcopal Church is a contributing resource within the proposed La Plata Historic District (CH-326).

Eligibility Recommended MARYLAND HISTORICAL Comments:	TRUST TRUST TRUST TRUST TRUST TRUST TRUST TRUST
Reviewer, OPS: Marie Time Time Time Time Time Time Time Ti	Date:

Page 8.2 P.A.C. Spero & Company September 1996/revised November 1998

9. Major Bibliographical References Survey No.: CH-62 (PACS C115)

See Continuation Sheet

10. Geographical Data

Acreage of nominated property
Quadrangle name <u>La Plata, MD</u>

Quadrangle scale <u>1:24,000</u>

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries state code county code

state

code

county

code

11. Form Prepared By

ame/title Caroline Hall/Ryan McKay

organization P.A.C. Spero & Company

date September 1996/revised November 1998

street & number 40 W. Chesapeake Avenue, Suite 412

telephone (410) 296-1635

city or town Baltimore

state Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposed only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

DHCP/DHCD

100 Community Place

Crownsville, MD 21032-2023

(410) 514-7600

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Christ Episcopal Church

SURVEY NO.: CH-62 (PACS C115)

ADDRESS: 100 Block of Charles Street, La Plata, Charles County

9. Major Bibliographical References (Continued)

- Brown, Jack D., et al. <u>Charles County, Maryland, A History</u>. Charles County Bicentennial Committee, 1976.
- Charles County Retired Teachers Association. <u>A Legacy: One- and Two-Room Schools in Charles County</u>. La Plata: Dick Wildes Publishing Company, 1984.
- Gottfried, Herbert and Jennings, Jan. <u>American Vernacular Design, 1870-1940</u>. Ames, Iowa: Iowa State University Press, 1988.
- Klapthor, Margaret Brown, and Paul Dennis Brown. <u>The History of Charles County, Maryland</u>. La Plata: Charles County Tercentenary, Inc., 1958.
- Martenet, Simon J. Martenet's Map of Maryland, Atlas Edition. Baltimore, 1866.
- Maryland Geological Survey. [1840] Map of Eastern Maryland with 1860 Additions. Copy on file at Maryland Historical Trust, Crownsville, MD.
- ivoire, J. Richard. <u>Homeplaces, Traditional Domestic Architecture of Charles County, Maryland</u>. La Plata: Southern Maryland Studies Center, 1990.
- Wearmouth, John M. <u>Charles County Railroad</u>. An unpublished paper on deposit at the Prince George's County Historical Society. August 1984.
- Ibid. <u>La Plata, Maryland, 1888-1988, 100 Years, The Heart of Charles County</u>. La Plata: Town of La Plata, 1988.

Maryland Comprehensive Historic Preservation Plan Data Sheet

Christ Episcopal Church; CH-62 (PACS C115) 100 Block of Charles Street, La Plata, Charles County

Historic Context:

MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geographic Organization:

Western Shore

Chronological/Developmental Period Theme (s):

Industrial/Urban Dominance A.D. 1870-1930

Prehistoric/Historic Period Theme(s):

Architecture; Religion

RESOURCE TYPE:

Category (see Section 3 of survey form):

Buildings; Private Ownership; Public Acquisition - Not applicable; Occupied; Not accessible; Church

Historic Environment (urban, suburban, village, or rural):


Village

Historic Function(s) and Use(s):

Church

Known Design Source (write none if unknown):

None





1 CH-62 2 Christ Episcopal Church Charles County, MD 3 Byan Mckax, 9/96 4 P.A.C. Spero and Company 40 W. Chosquele Ave, #4/12 Baltimae, MD 21204/ 5 100 Block of Charles Street East and South elevations of church North west view 61044



I CH-62 2 Christ Episcopal Church, Charles County, MO 3 Byan Mckar, 9/96 4 P.A.C. Spero and Company 40 West Chesapeake Ave, #4/12 Baltimore, MD 21204 5 100 Block of Charles Street West elevation 6 4 of 4



1 04-107 Charles County My - Ryn Make Internet appear to the party of the second And the twent Williams Egd eler thend church wast new



LO He DA 2 Const Epsepal Church 3 Ryan Mckay AFA: person may a reason to the Assiste was now for metalense 3.100 Block of Charles Street East elevation of Parish House wed view 2 cf 4/

Survey No.: CH-62 (PACS C115)

DOE ___yes ___no

Maryland Historical Trust Maryland Inventory of Historic Properties Form U.S. 301 South Corridor Transportation Study

1. Name: (indicat	e preferred name)	
historic Christ Episcopal Ch	urch	
and/or common		
2. Location:		
street & number 100 Block of	Charles Street	not for publication
city, town La Plata	_ vicinity of	congressional district
state Maryland	county Charl	es
3. Classificat:	Lon:	
Category Ownership districtpublic _x building(s)x privatebothsite	work in p Accessible ess x yes: rest considered licable no DPERTY: (give names	rogresseducationprivateentertainment residence rictedgovernment _x_religious
	Legal Descript	·
Land Records Office of Charl		liber 15
street & number 101 Catalpa	Drive	folio 129
city,town La Plata		state MD
6. Representat:	ion in Existing	Historical Surveys
title Inventory of Historic	Sites in Calvert, Charles,	and St. Mary's Counties
date 1980	1	federal <u>x</u> state <u>county</u> local
epository/survey records Ma	ryland Historical Trust	
city,town Crownsville		state Maryland

7. Description

Condition _excellent	deteriorated	Check one unaltered altered	Check oneoriginal site	date of move 1906
good fair	ruins unexposed	<u>x</u> altereu	<u>x</u> moved	date of move <u>1900</u>

Survey No.: CH-62 (PACS C115)

Resource Count: 1

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Christ Episcopal Church was previously inventoried by the Maryland Historical Trust in the 1970s; however, an extensive survey form was not completed. Christ Episcopal Church is a $1\frac{1}{2}$ -story Victorian Gothic Revival Church on the north side of Charles Street in downtown La Plata, Charles County. The church was originally constructed circa 1830 next to the courthouse in the town of Port Tobacco, replacing an earlier church destroyed in a storm. In 1906, after the Charles County seat had been moved from Port Tobacco to La Plata, the church was dismantled, moved to La Plata, and rebuilt in the Victorian Gothic Revival style. The church has a nave and side aisles, a centered arched entry, and an off-center 4-story bell tower at the southwest corner. In 1938, a parish hall was constructed and connected to the church by a hyphen.

The structure has an asphalt shingle, dual-pitch front-gable roof with five dormers on both roof planes. The church is of stone construction. All windows, including the dormer windows, are gothic-arch windows with stained glass, and there is a large gothic-arch window with a centered rose window on the south, or front elevation. The exposed elevations of the bell tower have thic-arch windows on the first three stories and gothic-arch louvers on the top level. The st and east elevations have four gothic-arch windows, and a projecting bay at the rear of the church. The bay on the west elevation has a wood door and steps to grade.

The parish hall, which is oriented perpendicular to the church, has an asphalt shingle, front-gable roof, an arched entry, and buttresses on the south and north elevations. The parish hall is of stuccoed concrete block construction, and it is connected to the church at the southwest corner. The windows are 8-light casements, and there are two exit doors at the rear.

There are no outbuildings associated with this property.

The property is located at the corner of Charles Street and Church Street in downtown La Plata. There is a residence now used as an office to the west, and parking lots for county buildings to the north. There are some mature trees located in front of the church along Charles Street. The property's setting is downtown La Plata, along the heavily travelled main street.

8. Significance

Survey No.: CH-62 (PACS C115)

Period Prehistori		ficance—Check and j Community planning	ustify below glandscape architectu	rereligion
1400-149 1500-159 1600-169 1700-179 1800-189	9archeology-historic 9agriculture 9architecture 9art 9commercecommunication	<pre>conservationeconomicseducationengineeringexploration/settlemen</pre>	law literature military	science sculpture social/ humanitarian theater
Specific d	ates circa 1830, 1906		Builder/Architect	
check:	Applicable Criteria: and/or	AB	CD	
	Applicable Exception	s:AB	CDEFG	i
	Level of Significanc	e:national	statelocal	

Prepare both a summary paragraph of significance and a general statement of history and support.

Christ Episcopal Church was erected in downtown La Plata in 1906, using building materials from the previous Christ Episcopal Church, located in Port Tobacco. The congregation is one of the oldest in the area, originally established by act of the provincial assembly in 1692.

Eligious architecture in the project area frequently melded vernacular residential building types with religious architectural elements such as bell towers and front-gable orientation. The degree of architectural pretention exhibited by the churches of the area depended upon congregation size, wealth, and denomination. The design of churches reflected both functional and symbolic concerns. Churches (as opposed to meeting houses) in the area, as well as the nation, almost invariably featured front-gables. The front-gable orientation was the logical exterior architectural accommodation of the lengthened nave so frequently utilized by denominations tracing their lineage ultimately to the Roman Catholic Church, rather than Eastern Orthodox Church. A bell tower not only called parishioners to worship, but also provided a visual symbol of the building's spiritual, rather than secular, function. Fenestration also frequently symbolized the building's function; rounded, Gothic arch, and pointed shapes helped distinguish the church from its secular neighbors.

Christ Episcopal Church was rebuilt in a Victorian Gothic Revival style. Most Catholic and Episcopalian churches built from 1845 to 1900 were built in the Gothic Revival style. The emergence of this style reflected the renewed religious intensity in the second quarter of the nineteenth century which is commonly referred to as the "Second Great Awakening". Religious leaders increasingly came to believe that the prevailing Greek Revival style was too pagan and that a more appropriate design would be one that harkened back to the religious spirit of the Middle Ages. Gothic Revival was also known as a picturesque style in that it rejected classical qualities and appealed to those which excited the Romantic mind. Vernacular Gothic Revival churches frequently featured pointed arches and a steeple but few of the embellishments found in urban examples. There was also an emphasis on verticality, which was achieved by steeply pitched roofs. The major variations involved the location of the steeple which, in turn, influenced the fenestration. Churches with the steeple located at the center of the facade have mmetrical fenestration with a three bay organization. They sometimes have an exposed gable in which the steeple is set behind the gable which is then frequently ornamented with stickwork,

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM
ESOURCE NAME: Christ Episcopal Church

SURVEY NO.: CH-62 (PACS C115)

ADDRESS: 100 Block of Charles Street, La Plata, Charles County

8. Significance (Continued)

shingling, or a round window. Placing the steeple away from the center of the facade resulted in asymmetrical fenestration and allowed room for paired windows or a triple window. The most elaborate variation featured a pair of steeples one located on each side of the church (Gottfried 1988: 250-254).

Christ Episcopal Church is located in Charles County in southern Maryland. The Native American inhabitants of southern Maryland from the Piscataway and Potobac nations were joined by European settlers beginning in 1634 with the establishment of St. Mary's City by Leonard Calvert. Successive waves of colonists took up tracts of land further inland from the Chesapeake Bay along the Patuxent and Potomac rivers and their tributaries. Charles County was formed in 1658 and Prince George's County was established in 1696. Settlement was confined to inland areas until road clearing began in the mid-eighteenth century as a result of the establishment of port towns and Maryland's rising population. Tobacco cultivation dominated the economic and social life of both Charles and Prince George's counties until the mid-nineteenth century when soil exhaustion necessitated agricultural diversification. The introduction of rail lines in 1873 linked Prince George's and Charles counties with the surrounding area, encouraging trade and settlement. While the suburbanization of Prince George's and Charles counties was ensured by e widespread availability of the automobile in the mid-twentieth century, these southern maryland counties have also retained their rural and agricultural character.

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM
ESOURCE NAME: Christ Episcopal Church

SURVEY NO.: CH-62 (PACS C115)

ADDRESS: 100 Block of Charles Street, La Plata, Charles County

8. Significance (Continued)

NATIONAL REGISTER EVALUATION

Christ Episcopal Church, constructed circa 1830, moved and rebuilt in 1906, was previously inventoried by the Maryland Historical Trust in the 1970s. The church is not eligible for the National Register of Historic Places. The property is not eligible under Criterion A, as research conducted indicates no association with any historic events or trends significant in the development of national, state or local history. Historic research indicates that the property has no association with persons who have made specific contributions to history, and therefore, it does not meet Criterion B. It is not eligible under Criterion C, as it is an undistinctive example of a common architectural style and it has been altered by side additions. The parish house, constructed in 1938, is also an undistinctive example of a common architectural style. The church must be evaluated as an early twentieth century building, and it does not represent a distinctive example of a late Victorian Gothic church. Finally, the structure has no known potential to yield important information, and therefore, is not eligible under Criterion D.

Eligibility Recommended Comments:	MARYLAND HISTORICAL TRUST Eligibility Not Recommended	
Reviewer, OPS:	Date: Date:	

Page 8.2 P.A.C. Spero & Company September 1996

9. Major Bibliographical References Survey No.: CH-62 (PACS C115)

See Continuation Sheet

10. Geographical Data

Acreage of nominated property

Quadrangle name <u>La Plata, MD</u>

Quadrangle scale 1:24,000

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries state code county code

11. Form Prepared By

me/title Caroline Hall/Ryan McKay

organization P.A.C. Spero & Company date September 1996

street & number 40 W. Chesapeake Avenue, Suite 412 telephone (410) 296-1635

city or town Baltimore state Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposed only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

DHCP/DHCD

100 Community Place

Crownsville, MD 21032-2023

(410) 514-7600

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

'ESOURCE NAME: Christ Episcopal Church

SURVEY NO.: CH-62 (PACS C115)

ADDRESS: 100 Block of Charles Street, La Plata, Charles County

9. Major Bibliographical References (Continued)

- Brown, Jack D., et al. <u>Charles County, Maryland, A History</u>. Charles County Bicentennial Committee, 1976.
- Charles County Retired Teachers Association. <u>A Legacy: One- and Two-Room Schools in Charles County</u>. La Plata: Dick Wildes Publishing Company, 1984.
- Gottfried, Herbert and Jennings, Jan. <u>American Vernacular Design, 1870-1940</u>. Ames, Iowa: Iowa State University Press, 1988.
- Klapthor, Margaret Brown, and Paul Dennis Brown. <u>The History of Charles County, Maryland</u>. La Plata: Charles County Tercentenary, Inc., 1958.
- Martenet, Simon J. Martenet's Map of Maryland, Atlas Edition. Baltimore, 1866.
- Maryland Geological Survey. [1840] Map of Eastern Maryland with 1860 Additions. Copy on file at Maryland Historical Trust, Crownsville, MD.
 - voire, J. Richard. <u>Homeplaces, Traditional Domestic Architecture of Charles County, Maryland</u>. La Plata: Southern Maryland Studies Center, 1990.
- Wearmouth, John M. <u>Charles County Railroad</u>. An unpublished paper on deposit at the Prince George's County Historical Society. August 1984.
- Ibid. <u>La Plata, Maryland, 1888-1988, 100 Years, The Heart of Charles County</u>. La Plata: Town of La Plata, 1988.

Maryland Comprehensive Historic Preservation Plan Data Sheet

```
Christ Episcopal Church; CH-62 (PACS C115)
100 Block of Charles Street, La Plata, Charles County
```

Historic Context:

MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geographic Organization:

Western Shore

Chronological/Developmental Period Theme (s):

Industrial/Urban Dominance A.D. 1870-1930

Prehistoric/Historic Period Theme(s):

Architecture; Religion

RESOURCE TYPE:

Category (see Section 3 of survey form):

Buildings; Private Ownership; Public Acquisition - Not applicable; Occupied; Not accessible; Church

Historic Environment (urban, suburban, village, or rural):

Village

Historic Function(s) and Use(s):

Church

Known Design Source (write none if unknown):

None

Form 10-300 (Dec. 1968)

UNITED STATE

ATL EPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE NATIONAL REGISTER OF HISTORIC PLACES INVENTORY - NOMINATION FORM

MD. HISTORICAL TRUST BOX 1704 ANNA

COUNTY:	
FOR NPS USE O	NLY
ENTRY NUMBER	DATE

5.	STISCOPACE STREET AND NUMBER: ST. ALBAI CITY DR TOWN: WASHING LOCATION OF LEGAL DESC	TOU	DIC.	STATE:		CODE					
	ST. ALBA	US				CODE					
	STREET AND NUMBER:		SE OF	MD.							
	EPISCOPAL	- DIOCE	SE OF	MD.							
	EPISCOPAL DIOCESE of MD.										
4.	OWNER OF PROPERTY DWNERS NAME:		0								
12			chelle	-							
	Entertoinment Museum		igious entific								
	Commercial Industria		vate Residence	_	er (Specify)						
	Agriculturol Governm	ent Par	k	Tra	nsportation	Comments 🔲					
	PRESENT USE (Check One or More as Appropriate)										
	Object	DOIN	Dening Consider			No:					
	Site Structure	Private Both	In Process Being Consider	ed 🗀	Unoccupied Preservotion work	Unrestricted 7					
	District Building	Public 🔎	Public Acquisition:		Occupied Z	Yes:					
	(Check One)		OWNERSHIP		STATUS	TO THE PUBLIC					
3.	CLASSIFICATION		0)****		STATUS	ACCESSIBLE					
-	MD, GHAS,										
	STATE CDDE COUNTY: CDDE										
		LA PIATA									
CITY OR TOWN:											
STREET AND NUMBER:											
2.	2. LOCATION										
	AND/OR HISTORIC:										
	CHIRIST CHURCH, PORT TOBACCO Parish										
			0								

			D FIEL	D SHEET	CH-62
7.	DESCRIPTION		N. IV.		
	CONDITION		(Check	One)	
	CONDITION	Excellent Good [Foir Deterioro	ted Ruins	Unexposed
	INTEGRITY	(Check	One)	∫Ch.	eck One)
	INTEGRITI	Altered _	Unoltered 🔃	Moved	Original Site
	DESCRIBE THE PE	ESENT AND ORIGINAL (If &	nown) PHYSICAL APPEAR	ANCE	

CHT STONE LONSTRUCTION "A" ROOF & FLARE AT SIDES TO ALLOW SIDE AIGLES - (LATER ADDITION). ROOF PUDGE RUNS N to S. PUDGE 2 STOREMS & AISLE ADDITION EAVES ISTOREY, 6 BAYS Front. (D. W. D. W. W. W.) LARGE ARCHED "(GOTHIC" WINDOW AT ATTIC LEVEL (3, EIE.) SQUARTE BELL TOWER. 2 STOREYS. AT S. W. LOZNER. LOUVERED OPENINGS AT 4 SIDES TOP. ROOF ASPHALT SHINGLE 4 BAYS ETSIDE IST, FLOOR IZUZI-BOTHIC

4 DOZMERS E+ LO - PEAKED "A" FrAME "abitle"

NEW MASONRY PAIRISH HALL AT REAR (N) of CHURCH - CONNECTED TO CHURCH By Hyphen,

PARISH HOUSE (PARSONAGE) TO W SIDE. SOME STONES OUT WITH INTITIALS + PATES PROE TO REVOLUTION.

Pre-Columb	oian 🗌	16th Cente	ury 🗌	18th Centu	Jry 🗌	20th Century	
15th Centu	у 🗆	17th Cent	ury 🗌	19th Centu	ILA 🛅		
PECIFIC DATE(S)	If Applicab	le and Known)					
REAS OF SIGNIFIC	ANCE (Ch	eck One or More a	s Appropria	te)			
Abor iginal		Education		Political		Urbon Planning	
Prehistori	с 🗌	Engineering		Religion/Phi-		Other (Specify)	
Historic		Industry		losophy			
Agriculture		Invention		Science			
Art		Landscope		Sculpture			
Commerce		Architecture		Social/Human-			
Communicati	ons	Literoture		itarian			
				TISA			
Conservation		Militory		Theater			
TATEMENT OF SIGN	NIFICANCE	Music (Include Person	TVILE	Transpartation s, Events, Etc.)	<u> </u>	it SIDE A	152
Por For EAVELI Mor	FOR POR	Music (Include Person FORE STONE TOB TURTY	HODE BACCO	Transpartation s, Events, Etc.) twrt (Cout F BIRIC STO LA	K(P) NE PLAT	by of call	CIVI CT

SEEINSTRUCTIONS

O MAIOD	BIBLIOGRAPHICAL	D.	EDENCES	N	+	R. Maria		
7. MAJOR	DIDLIOGRAFIICAL	. Kini	FERENCES					
							,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
10. GEOGI	RAPHICAL DATA				.~			
	LATITUDE AND LONG ING A RECTANGLE L				O R	DELINING THE CENTER		
CORNER	LATITUDE		LONGITUE	DE		LATITUDE	LONGITUD	E
	Degrees Minutes Secon	nds	Degrees Minutes	Seconds		Degrees Minutes Seconds	Degrees Minutes	Seconds
NW	0 ,	19	0 ,	10		0 , "	0 '	99
NE	0 ,	19	0 ,	19				
SE	0 ,	19	0 ,	10				
SW	ō ,	10	0 ,	10				
LIST ALI	STATES AND COUN	TIES	FOR PROPERTI	ES OVER	LA	APPING STATE OR CDUNTY BO	DUNDARIES	,
STATE:				CODE	_ (COUNTY		CODE
					1			
STATE:				CDDE	- '	COUNTY:		CODE
					1			CODE
STATE:				CDDE	- 1	CDUNTY:		CODE
					\perp			0005
STATE:				CODE	- '	COUNTY:		CODE
		.,,			1			
	PREPARED BY				-			
NAME A	R. ch.	0	Proors	2				
ORGANI	ZATION	4	MOVE	7		A	DATE	
OKCAN	M.H.	7.						
STREET	AND NUMBER:							
CITY OR	TDWN:				S	STATE AA A		CDDE
	Orrnas	4				rua.		
12. STAT	E LIAISON OFFICE	RCE	RTIFICATION		1	NATIONAL REGIST	ER VERIFICATIO	N
					T			
	1		- Officer for th	o No				
	e designated State L Historic Preservation					I hereby certify that this p	roperty is included	in the
1						National Register.		
	5), I hereby nominate							
	National Register a							
	ated according to the							
	by the National Park			iiiiie iided		Chief, Office of Archeolog	gy and Historic Pre	servation
	of significance of the National St							
1	National St	ale	Bocar					
						Date		
Name						ATTECT.		
						ATTEST:		
Title								
						Keeper of The	National Register	
Date						Date		

